



Quote #Q15.2.802#R3
February 8, 2017

Via Email:kscholl@northhuron.ca

Attn: Kim Scholl
Township of North Huron
99 Kerr Drive,
Wingham, ON N0G 2W0

RE: North Huron Recreation Centre – Pool Renovation

POOL RENOVATION PROPOSAL

Includes the Following

- Remove and dispose of existing floor liner, including liner at stairs, benches, ramp and dividing wall.
- Hydroblast all exposed concrete to remove any residual glue or loose concrete.
- Waterproof the floor and all exposed concrete areas before installing tile.
- Install tile on pool floor, stairs, benches, ramp and dividing wall (Dal-Tile group 1 or 2 for field tile, Group 4 for Contrasting tile).
- Use Laticrete 245 Platinum mortar for tile setting.
- Use Laticrete 1500 Series sanded grout.
- Supply and install new 24"x24" frames and grates on all four main drains (VGBA compliant).
- Provide a 5 year tile and liner warranty.
- Start up and commissioning.
- Provide 60 mil PVC membrane to pool floor/wall joints. There will be a PVC termination bar on the pool slab and stainless steel walls
- Final cleaning

ADD: \$180,098.00

Option A

- Use Laticrete Spectralock PRO epoxy grout.
- Includes 25 year warranty from Laticrete for labour and materials
- 5 year tile warranty from Dal Tile
- 15 year labour and materials warranty from Acapulco Pools

ADD: \$25,739.00

Option B

- Supply and install Hanovia PMD200 E1/6AW UV system.
- Includes one day training session.
- Medium pressure UV
- Inline strainer

ADD: \$31,470.00

Option C

- Pool walls are experiencing corrosion and we recommend covering the walls with a PVC membrane
- Membrane to be mechanically fastened on the pool floor and under the tile border

ADD: \$32,436.00**Option D**

- Provide a working surface over the pool tank to allow scissor lifts to operate over the pool
- New SS straps for the HVAC system
- Painting of the HVAC system, beams and piping in the ceiling space
- Removal of working surface over the pool
- Acapulco will bid this work to local contractors
- Painting specification to be prepared by others
- Acapulco will add a 15% markup to the bids for this work. This markup is included in the budget amount

BUDGET: \$40,000 - \$44,000**Option E**

- Provide iron remover for the makeup water systems for the swimming pool. Due to cost considerations we did not include a system large enough to remove iron when filling the pool. It would be more economical to fill the pool slowly or purchase the water and have it shipped by trucks when the entire pool is refilled which does not occur often.
 - 25 gpm flow rate
 - Chlorination tank
 - 2 filter tanks
 - Manual backwash and draining
 - Chemical pump
 - Chemical feeder
 - Labour to install
 - PVC pipe fittings and valves
 - Electrical hookup

ADD: \$27,982.80**Note:** HST is Extra**Assumptions**

Pool work to commence in 2017 and be complete by December 2017

Schedule

Duration of work subject to options accepted 8-10 Weeks

Warranty**Tile with Epoxy Grout**

Laticrete	25 year labour and materials
Acapulco	15 year labour and materials
Dal Tile	5 year materials

PVC Membrane Walls and Wall Floor Interface

Acapulco	5 year labour and materials
----------	-----------------------------

By Others

- There will be no work to the ceiling baffles
- No work to the pool deck
- Any work to the HVAC system

Thank you for the opportunity to provide you with this proposal. Our proposal is valid for sixty (60) days. Please feel free to contact me if you have any questions regarding this proposal.

Sincerely,

ACAPULCO POOLS LIMITED

Bernhard Gall
President

BG/gk